Commonwealth of the Northern Mariana Islands Integrated 305(b) and 303(d) Water Quality Assessment Report



Traditional Sailing Canoe, Saipan

Division of Environmental Quality Revised: October, 2008

Editor: Peter Houk

Authors: Brian Bearden, Frances Castro, Peter Houk, Derek Chambers, and Clarissa Bearden

TABLE OF CONTENTS

Introduction to this Report and the 305(b) Process
Executive Summary
Background
Background of CNMI and its Waters
Surface Water Assessment 17
Beach Water Quality Monitoring Program17Background and Methodology17Results and Discussion22Lagoon and Coral Reef Biocriteria Monitoring Programs30Background and Methodology30Results and Discussion31Integrated 305b and 303d Waterbody Classification35(CALM) Waterbody Classification35303(d) Priority List36Relevant Issues Associated With Water Quality Permitting and Pollution42Current program activities and projects relevant to 303(d) listed waters42Laolao Bay Stormwater Control (Relevant to Category 4b Waters for 'SEB 2, 3')30
42 Obyan Beach Stormwater Control (Relevant to Category 4b Waters for SEB 4') 42
Talakhaya Restoration Project (Relevant to Category 4b Waters for 'Talakhaya')
Groundwater Assessment
Numeric Groundwater Standards
Literature Cited

Introduction to this Report and the 305(b) Process

Section 305(b) of the federal Water Pollution Control Act (Clean Water Act) requires that states and territories monitor the quality of their surface and groundwaters and produce a report describing the status of their water quality. This report is referred to as the 305(b) which will be used by the United States Environmental Protection Agency (EPA), US Congress, and the public, to evaluate: (1) whether U.S. waters meet water quality standards, (2) the progress made in maintaining and restoring water quality, and (3) the extent of remaining problems. EPA requires all impaired waterbodies, from unknown pollution sources, to be placed on the 303(d) list for further studies regarding the sources and quantities of various pollutants. The EPA consolidated assessment and listing methodology (CALM) categories were used to classify all assessed waterbodies in the CNMI during 2006 and 2007. The Division of Environmental Quality under the Office of the Governor is responsible for preparing the Commonwealth of the Northern Mariana Islands (CNMI) 305(b) report, and subsequent 303(d) listings.

Executive Summary

The health and economic wellbeing of the people of the Commonwealth of the Northern Mariana Islands (CNMI) depend upon good water quality. Tourism is a major driving force behind the CNMI economy. Tourists come to see beautiful sandy beaches, clear blue water, and diverse coral reefs. The CNMI has over 250 species of coral (Randall, 1995) over 850 species of fish (Myers, 2000), and over 1000 marine invertebrates (Paulay 2003) that inhabit our corals reefs. CNMI residents rely upon clean water and healthy reefs for fishing and recreation. Healthy marine environments require clean water that remains within a narrow range of water quality parameters. Under the current development pressure we are challenged to maintain and improve our water resources.

Both point and non-point source pollution are responsible for lowering the quality of the CNMI's waters. Sewage outfalls, failing sewer collection systems, sedimentation from unpaved roads, poor erosion control practices during development, urban runoff, and reverse osmosis discharges are the most significant stressors to our water quality. Most of CNMI's wetlands that naturally filter stormwater prior to its marine discharge were filled for agriculture use and urban development during the Japanese occupation period. Presently, wetlands comprise less than 5% of the land, and are patchily distributed around Saipan and Tinian Island, presenting enhanced challenges to improving our surface waters. The largest groundwater problems in the CNMI are high chlorides resulting from over-pumping of the basal aquifer in an effort to keep up with the increasing population demand, and nutrient and bacteria input from septic systems.

Eighty beach locations are monitored for traditional surface water quality parameters and *Enterococci* bacteria levels. Unsurprisingly, most microbiological violations were recorded for monitoring stations in close proximity to large, heavily populated drainages, especially during rain events. Bacteria enriched waters are mainly associated with the Saipan lagoon, representing CNMI's most developed coastline.

Two biocriteria monitoring programs have been established by the Division of Environmental Quality (DEQ) in conjunction with the Coastal Resources Management Office. The Saipan Lagoon monitoring program collects data regarding the abundances of fast growing macroalgae, seagrass, and corals within each lagoon habitat. Our nearshore reef monitoring program collects data on the coral assemblages that inhabit our reef slopes. These data provide an evaluation of the benthic communities based upon know relationships between ecological measures and water quality.

Throughout CNMI's 53.7 km of beach coastline 69% was assessed during 2006 – 2007, indicating that 86% of all monitored waterbodies were impaired and remain 303(d) listed for various reasons. Saipan has the largest percentage of impaired waters (92%) due to bacteria violation and biological data. The impaired waters of Tinian (100%) and Rota (80%) are listed mainly due to historical nutrient data, an artifact of CNMI's stringent orthophosphate and dissolved oxygen water quality standards that do no represent ambient conditions. While these numbers may seem high the guidance materials from

EPA that drive this reporting process requires an 'impairment' ranking for all waters that are not proven pristine.

The CNMI Division of Environmental Quality has implemented several programs that address and regulate development, agriculture, fuel storage, pesticide use, and other potential contributing pollutants. All projects and ongoing issues that have or potentially may affect CNMI's water quality are furthered within.

Background

Background of CNMI and its Waters

The Commonwealth of the Northern Mariana Islands (CNMI) consists of two geologically distinct island chains located at 145° E, between $14^{\circ} - 21^{\circ}$ N (Figure 1). The Southern Mariana Islands are between 5 and 20 million years old and consist of raised, limestone reef bedrock resultant from high sea level stands prior to the Holocene (~6,000 before present) (Karig, 1975, Mrozowski and Hayes, 1980). The Northern Islands lie to the northwest, residing on the still active Mariana Ridge. This report contains information from the southern islands of Saipan, Tinian, Aguijan, and Rota, where the vast majority of the population lives (Table 1). Saipan is the capital of CNMI, and the largest and most inhabited of the islands. Threats to water quality are greatest in Saipan, where DEQ operations are based, resulting in more resources being dedicated to understanding these impaired waters.

Surface Water Quality Background

The CNMI has two classes (AA and A) for marine water use and two classes (1 and 2) for fresh surface water use. All fresh surface water bodies in the CNMI (wetlands, intermittent streams, and perennial streams) are Class 1, meaning that these waters should remain in their natural state with an absolute minimum of pollution from any human-caused source. On Saipan Island there are approximately three perennial streams, one lake, and several isolated wetland regions (Figure 2). On Tinian there are several wetlands, no lakes, and only intermittent streams (Figure 3). On Rota there are several perennial and intermittent streams, no lakes, and no wetlands (Figure 4). Wetlands and perennial streams comprise less than 5% of the land, and are patchily distributed around Saipan and Tinian Island. Some of these resources are used for drinking water and recreation but are not tested by the DEQ Lab on a regular basis due to their low abundance and use.

Wetlands can be found on the islands of Saipan, Tinian, Rota, and Pagan, however they cover less than 2% of the CNMI at the present time (based on current CNMI GIS layers). Despite their low occurrence, wetlands provide habitat for unique and endangered plants and animals present in CNMI. Wetlands also serve other functional purposes such as storm runoff water storage and pollutant uptake. For a more detailed look at CNMI's wetlands and their functional roles one can refer to CNMI's "National Wetland Inventory" document (Prepared by US Fish and Wildlife, 1989, CRM Office). This document states there are approximately 600 acres of wetlands in CNMI. The "Commonwealth of the Northern Mariana Islands Wetlands Conservation Plan" states that only 36% of the original wetland acreage still exists (CRM Office), losses due to filling are as follows: Garapan - 200 acres, San Roque - 50 acres, Flores Pond - 130 acres, Lake Susupe area - 200 acres, and Kagman and Lower Base - 600 acres. Saipan was heavily farmed during Japanese times (pre-World War II), which resulted in filling of

wetland areas to make them suitable. Increasing development continues to threaten wetlands on all of the islands but current regulations are in place to mitigate these impacts for all future projects.

The majority of the coastal marine waters are Class AA, meaning that these waters should remain in their natural pristine state as nearly as possible with an absolute minimum of pollution or alteration of water quality from any human-related source or actions. The uses protected in these waters are the support and propagation of marine life, conservation of coral reefs and wilderness areas, oceanographic research, and aesthetic enjoyment and compatible recreation inclusive of whole body contact (e.g. swimming and snorkeling) and related activities (Table 2). Class A waters are only found near the two largest oceanic sewage outfalls and the ports of the CNMI. Class A waters are protected for their recreational use and aesthetic enjoyment; other uses are allowed as long as they are compatible with the protection and propagation of fish, shellfish, and wildlife, and recreation in and on these waters of a limited body contact nature.

In the case of the CNMI, as with all island nations, discussions about surface water quality must include information regarding the status of nearshore marine communities. Marine communities can shift in response to nutrient enrichment (e.g. water quality impairment) (Fabricius and De'ath 2001, Houk and van Woesik 2008). Similarly, changes in temperature, salinity, pH, dissolve oxygen, and other water quality criteria will also affect coral reef assemblages (Valiela 1995). At any particular time, water quality measurements are affected by rainfall or storm events, tidal fluctuations, and other atmospheric and oceanographic conditions. This dynamic nature makes all water quality data very difficult to properly assess a region, project, or pollutant source, without appropriate sample sizes and design. Another way to examine the quality of the water is to examine the nearshore assemblages that are bathed by watershed discharge. In this report we utilize biological criteria (data regarding our nearshore coral reef assemblages) to compliment water quality data when making our assessments.

Both point and non-point source pollution are responsible for lowering the quality of the CNMI's surface waters. Sewage outfalls, failed sewer collection facilities, sedimentation from unpaved roads and development, urban runoff, reverse osmosis discharges, and nutrients from golf courses and agriculture are the most significant stressors to surface and marine water quality.

Table 1. Statistics for the Southern Mariana Islands.

Resource	Value
Surface area of CNMI	457.1 sq km
Surface area of Saipan	120.4 sq km
Surface area of Tinian	101.5 sq km
Surface area of Rota	85.0 sq km
Population (total)	69,221 (in 2000)
Saipan Population	62,392 (in 2000)
Rota Population	3,282 (in 2000)
Tinian Population	3,540 (in 2000)
CNMI Residents	21,306 (in 1995)
Alien workers	37,540 (in 1995)
Tourists	497,601 (in 2001)
Length of perennial and intermittent streams on Saipan	95.5 km
Area of freshwater and tidal wetlands on Saipan	2,808 sq km
Area of Saipan lagoon	30,750 sq km
Length of Saipan coastline	75.52 km
Length of Rota coastline	55.84 km
Length of Tinian coastline	58.65 km
Area of bays (Lau Lau Bay, Saipan)	10,662 sq km
Area of Saipan marina (Smiling Cove)	0.1 sq km
Area of CNMI EEZ	414,398 sq km (approximate)

CNMI Department of Commerce Statistical Yearbook 1996 (based on 1995 census)

CNMI Geographic Information System

CNMI Department of Commerce

Figure 1. The Mariana Islands.





Table2. Class A Waters, CNMI.

Water Body	Reason for Class A designation
Puerto Rico Industrial, Saipan	Commercial port and municipal waste outfall
Agingan Point, Saipan	Municipal waste outfall
East Harbor, Rota	Commercial port
West Harbor, Rota	Commercial port
San Jose Harbor, Tinian	Commercial port

Kilometers n

Figure 2. Class 1 waters of Saipan: watersheds (black, outlined), intermittent streams (blue), wetlands (green), and coral reefs are shown in dashed black lines.

Figure 3. Class 1 waters of Tinian: watersheds (black, outlined), intermittent streams (blue), wetlands (green).






Figure 4. Class 1 waters of Rota: intermittent streams (blue), wetlands (green).

Groundwater Background

The Northern Mariana Islands formed as the result of arc volcanism west of the Pacific and Philippine plate junction. The geology of the southern islands suggests they were once submerged below sea-level, allowing a layer of coral reef to form over the volcanic rock. As a result of repeated fluctuations in sea-level and tectonics, the southern islands of Saipan, Tinian, Rota, Aguijan, and Farallon de Medinella currently comprise a predominantly limestone bedrock (Randall, 1995). This geological nature has produced two types of aquifers. In isolated, high-elevation areas, geology has created a situation where limestone fresh water aquifers overlie an impermeable volcanic layer, yielding a good and relatively protected supply of drinking water. However, the majority of the fresh water is found in the basal aquifer with a fresh water lens sitting on top of sea water, separated as a result of differences in density of the fluids.

The location and distribution of the fresh water aquifers are of extreme importance in the CNMI because the vast majority of drinking water comes from aquifers. The largest groundwater problem in the CNMI is high chlorides resulting from over-pumping of this basal aquifer in an effort to keep up with the increasing population demand. Over-pumping of groundwater can result in saltwater intrusion of the basal aquifer. The thickness of the freshwater lens on top of the saltwater is related to several factors, including extent of recharge areas, geology, and proximity to the coastline. Saltwater intrusion is reversible and does not cause permanent damage to the surrounding aquifer. The chloride problem only exists on the island of Saipan, but new developments initiated on Tinian and Rota may affect the basal aquifers there if future well drilling is not monitored or managed properly.

To protect the basal aquifer from saltwater intrusion the drilling of new water wells needs to be closely monitored. New well explorations should only be considered in areas where the thickness of the freshwater lens is identifiable and adequate. Other means of protecting the basal aquifer from saltwater intrusion are to control and limit the pumping rate of existing wells, and closely monitor the sample results of existing well for chlorides, conductivity and total dissolved solids.

The Safe Drinking Water/Groundwater Management Program has been compiling a database of wells in the CNMI over the past three years (2005-2008). There are currently 513 wells in the database. This total includes active and inactive drinking water, irrigation, exploratory, under ground injection, and monitoring wells. Of these 513 wells, 13 are located on Rota, 10 on Tinian, and the rest on Saipan. Of the 490 Saipan wells, 206 are owned by the Commonwealth Utilities Corporation (CUC - the local municipal water utility), while the other 284 wells are owned by other government entities, private companies or individuals.

On Saipan, there are several uses of groundwater including human consumption (public water supply systems) and irrigation for crops and golf courses. The CNMI is heavily dependent on tourism and garment factories for the local economy. Due to the high level

of chlorides in the public water system, major hotels and factories along the coast drill seawater wells and use reverse osmosis treatment for their private water supply.

The high level of chlorides in the public water supply on Saipan is a result of over pumping the municipal wells (which promotes salt water intrusion) to keep up with the demand for water. The 136 wells owned by the public utility company on Saipan theoretically produce enough water to meet the demands of the island. However, the real demand for water is significantly greater than the theoretical demand because of leaks in the municipal and homeowner water distribution systems (Army Corps, 2003). The production can not keep up with the demand and the leaks, so many neighborhoods on Saipan only receive water via the distribution system for several hours a day.

A concern on Saipan is the presence of coliform bacteria in the untreated (unchlorinated) well water. In March 2006 bacteriological testing of these samples revealed that approximately 60% of the wells tested positive for total coliform bacteria while 10% tested positive for E. coli bacteria. This contamination is a perceived result of high concentrations of septic systems in several villages that are not served by the sewer system that were improperly constructed.

An emerging concern on Saipan is nitrate contamination of the groundwater. CUC monitors for nitrate and nitrite at 45 sites throughout the public water distribution system. In June of 2006, one violation was noted from Saipan's southern water distribution system. While this was the first exceedance since monitoring began in 2001, one additional violation was noted in December 2006, followed by eight in June 2007, with levels as high as 14 mg/l (the MCL is 10 mg/l). Apparently, the concentration of nitrates in the groundwater fluctuates rapidly as three sites with over 14 mg/l in June 2007 had only 6 and 8 mg/l two weeks later. Rainfall is believed to play an important role in the variability of nitrates in the groundwater. In March 2008, the University of Guam Water Environmental Research Institute (WERI) funded a study to determine the relationship between rainfall and nitrate concentration in Saipan's groundwater that has just started.

The majority of the population of Saipan resides on the western side of the island. The villages of Garapan, Chalan Laulao, Susupe, Chalan Kanoa, and San Antonio are estimated to have concentrated sixty percent of the total island's population within twenty percent of the available landmass on Saipan. Meanwhile, the majority of the municipal water supply wells, pumping from the basal aquifer, are located in the southern part of the island. There is a smaller concentration of municipal wells located at higher elevations in the central part of the island, and a few springs, that serve the other forty percent of the population of Saipan.

At the present time the island of Rota, with a population of about 3,000, receives its municipal water from two springs (Water Cave and Onan Cave) and three newly drilled wells. The wells are drawing water from the high level aquifers and are not susceptible to salt water intrusion. However, the springs on Rota are suspected to be groundwater under direct influence of surface water (GUDI). Presently, DEQ is initiating monitoring of turbidity changes in accordance with the seasonal changes in order to determine if

further filtration should be required. Tinian on the other hand, with a population of about 3,200, gets its municipal water from two Maui type wells also suspected of GUDI and three deep wells. Both Tinian and Rota have not had water demands that lead to overpumping of the aquifers.

Background on DEQ Programs to Correct Impairments

The CNMI Division of Environmental Quality has implemented several programs that address and regulate development, agriculture, fuel storage, pesticide use, and other potential pollutants. All programs are mentioned below, however, further information regarding the present status and pertinent findings for each program are located in sections III and IV of this report.

There are several DEQ programs which deal with regulation and enforcement of pollution sources that may potentially affect water quality. The DEQ wastewater and erosion control branch reviews permit applications that deal with the Clean Water Act and section 401 territory water quality certifications. The DEQ non-point source (NPS) pollution branch addresses stormwater runoff concerns at the watershed level through education, outreach, and demonstration projects. The NPS branch administers EPA 319 grants and reviews permits to ensure compliance with the federal 6217 NPS program. The safe drinking water branch regulates public drinking water systems, well drilling, and underground injection wells. The air and toxic management branch deals with hazardous sources of pollution which may affect CNMI's waters. Finally, the above and underground fuel storage and pesticide branch deals with the legal and illegal storage of contaminants that often pose threats to CNMI's waters.

Surface Water Assessment

Beach Water Quality Monitoring Program

BACKGROUND AND METHODOLOGY

The Division of Environmental Quality surveillance laboratory was established by the Commonwealth of the Northern Mariana Islands to provide monitoring data required under the Safe Drinking Water Act (P.L. 93-523). The data generated by the laboratory are used to evaluate the quality of drinking and recreational waters in the Commonwealth. Therefore, a quality assurance plan is essential in the generation of these data and is an important part of the day-to-day activities of the laboratory. The DEQ Environmental Surveillance Laboratory Quality Assurance Manual includes Standard Operating Procedures (SOPs) for sampling, testing, reporting, and providing quality assurance for water quality parameters. There are two primary functions of the quality assurance plan: 1) it assures that proper quality control practices are implemented in day-to-day laboratory task, and 2) it assures that the reported data are valid, and are of a known precision and accuracy. Although the success of the program depends upon the training, professional pride and awareness of each individual technician, final responsibility for the reliability of reported analytical results rest with the Environmental Surveillance Laboratory Supervisor.

The microbiological and chemical parameters that the Division of Environmental Surveillance Laboratory currently monitors includes: salinity (&), dissolved oxygen (% D.O.), temperature (°C), pH, turbidity (NTU), and *Enterococci* bacteria (cfu/100ml). Orthophosphate (PO4) and Nitrates (NO3) were not monitored during 2006 - 2007 because DEQ recently procured new equipment that enhances their capability, and just recently was our QA/QC approved by EPA. The development of the CNMI Water Quality Standards were largely based upon the review of existing water quality standards for other tropical islands, and unfortunately not specific to the CNMI (Table 5), and furthered below.

On a weekly basis, DEQ monitors 39 fixed stations along Saipan's most frequented west coast beaches for microbiological and chemical parameters (Figure 5). Six beaches on the northeast coast and six beaches on the southeast coast are monitored on a 8-week rotational basis, and monthly during the non 8-week cycle, because the quality of the water is consistently good and/or a smaller population uses these waters. Eleven sites around Managaha Island, a small (~1.5 km coastline) island located within the Saipan Lagoon, are also monitored on a 8-week rotational basis, and monthly during the non 8-week cycle (Figure 6). On Tinian and Rota DEQ monitors eleven and twelve locations, respectively (Figures 7 and 8), that are frequently used by the community.

Because of the rarity of fresh, surface waters in the CNMI (<2.5% of CNMI surface area), and the lack of public use, there is no regular monitoring to support this waterbody assessment process at the present time.

The goal of the DEQ Lab Surface Water Quality Monitoring Program is to assess CNMI's waterbodies for compliance with recreational uses and aquatic life uses. EPA guidance material was used assign each water body as 1) non-supportive, 2) partially supportive, and 3) fully supportive for use (Table 6).

PARAMETER	CLASS AA	CLASS A	CLASS 1	CLASS 2
Fecal Coliform	$GM^{1} < 200$	$GM^1 < 200$	$GM^{1} < 200$	$GM^{1} < 200$
(CFU/100 ml)	< 400	Never > 400	Never > 400	Never > 400
Enterococci (CFU/	GM < 35	GM <125	GM < 33	GM < 90
100 ml)	< 104 Single Sample	< 276 Single Sample	< 61 Single Sample	< 108 Single Sample
E. coli			GM < 126	GM < 126
			< 235 Single Sample	< 406 Single Sample
PH	7.5 - 8.6	7.5 - 8.6	6.50-8.50	6.50 - 8.50
NO ₃ - N (mg/L)	< 0.20	< 0.50		
Total Nitrogen	< 0.4	< 0.75	< 0.75	< 1.50
(mg/L)				
Orthophosphate PO ₄	< 0.025	< 0.05	< 0.10	< 0.10
(mg/L)				
Total Phos	< 0.025	< 0.05	< 0.10	< 0.10
$PO_4 (mg/L)$				
Ammonia (mg/L)	< 0.02	< 0.02	< 0.02	< 0.02
(un-iodized)				
Dissolved O ₂ (%)	> 75	> 75	> 75	> 75
Total Filterable	5	40	5	40
Suspended Solids				
$\frac{(mg/L)^2}{2}$	10	10	2004 1 250	
Salinity $(\%)^2$	10	10	20‰ or above 250	20‰ or above 250
			mg/L	mg/L
Total Dissolved			500 mg/L	500 mg/L
Solids (mg/L)	1.0	1.0	1.0	1.0
Temperature (°C) ²	1.0	1.0	1.0	1.0
Turbidity (NTU) ²	0.5	1.0	0.5	1.0
Radioactive	Discharge prohibited	Discharge prohibited	Discharge prohibited	Discharge prohibited
Materials	2	2	2	2
Oil & Petroleum	ND ³	ND ³	ND ³	ND ³

Table 5. CNMI's pertinent water quality standards.

¹GM - Geometric mean in not less than four samples over a 30 day period. ² Shall not exceed ambient by more than the stated value. ³ ND - Non-detectable.

Table 6. Criteria for waterbody classification.

Degree of Aquatic Life Use Support	Criteria
Fully Supporting	For any one pollutant, WQS exceeded in ≤10 percent of measurements.
Partially Supporting	For any one pollutant, WQS exceeded in 11 to 25 percent of measurements.
Not Supporting	For any one pollutant, WQS exceeded in >25 percent of measurements.

Figure 5. Saipan Island beach water quality monitoring locations, biological criteria monitoring stations are indicated by the stars.




Figure 6. Managaha Island beach water quality monitoring locations, biological criteria monitoring stations are indicated by the stars.




Figure 7. Tinian Island beach water quality monitoring locations, biological criteria monitoring stations are indicated by the stars.





Figure 8. Rota Island beach water quality monitoring locations, biological criteria monitoring stations are indicated by the stars.



RESULTS AND DISCUSSION

Based upon *Enterococci* bacteria data, Saipan had the largest number of waterbodies that received a non-supportive ranking for recreational use (16 sites) compared with Managaha, Tinian, Aguijan, and Rota, where no sites were non-supportive, and only 7 were listed as partially supportive between 2006 and 2007 (Table 7 - 9). There was a large enough sample size for Saipan to conduct regression analyses between rainfall (independent variable) and Enterococci bacteria counts (dependent variable) (Table 7). Rainfall explained a significant amount (p<.05, regression analysis) of the variance in bacteria levels at 9 monitoring locations around Saipan (Table 7) (Figure 9 and 10). This is a substantial decrease from 2006 when 28 beaches had significant ties between bacteria levels and rainfall, mainly in the northern part of Saipan. Unfortunately, the lack of a significant relationship is not due to decreased bacteria in the waters as our results show increases in bacteria levels since 2006 at these sites. This increase is a hypothesized consequence of non-rain associated, sewage collection system failures over the past two years, highlighted a potential problem with the current system. Conversely, in the south of Saipan, the completion of the new sewer line corresponded with a decrease in bacteria levels, all sites here are now classified as partially or fully supportive (stations WB 30 – 37, Table 7).

In Rota, impaired waterbodies were associated with marinas and boat launching areas, and in one instance urban runoff, while the remaining waters were found to be in excellent quality. These findings are consistent with our 2006 reporting. Only three sites

on Tinian were classified as partially supportive, all are affiliated with relatively large watersheds, while the remaining had consistently low bacteria levels. Regressions with rainfall data were all not significant for Tinian monitoring sites, and much stormwater is discharges through the porous limestone rock as groundwater.

Data were also assessed for several other parameters including pH, dissolved oxygen, salinity, and temperature. These data showed little variation over the past two years, and all monitoring locations were ranked as fully supportive based upon them. Despite the fact that they are not presented in tabular format they were used to make final site rankings. Chemical parameters for orthophosphate (PO4) and nitrates (NO3) were not monitored during 2006 – 2007 as DEQ was procuring, setting up, and gaining EPA approval for their new flow injector analysis (FIA). In 2008 DEQ has begun sampling for nutrient criteria.


Beach Identifier	Beach Name	2006 Sample Size (n)	2007 Sample Size (n)	Percent Violations (Enterococci) 2006	Percent Violations (Enterococci) 2007	Rankings 2006	Rankings 2007	R ²	P Valu	e
WB 1	Wing Beach	51	34	7.8	14.7	3	2	0.01	>0.05	
WB 2	PauPau Beach	51	34	5.9	20.6	3	2	0.01	>0.05	
WB 3	Nikko Hotel	51	34	3.9	23.5	3	2	0.01	>0.05	
WB 4	San Roque School	51	34	11.8	14.7	2	2	0.01	>0.05	
WB 5	Plumeria Hotel	51	34	2.0	17.6	3	2	0.00	>0.05	
WB 6	Aqua Resort Hotel	51	34	3.9	17.6	3	2	0.02	>0.05	
WB 7	Tanapag Meeting Hall	51	34	35.3	35.3	1	1	0.01	>0.05	
WB 8	Central Repair Shop	51	34	23.5	35.3	2	1	0.00	>0.05	
WB 9	Sea Plane Ramp	51	34	2.0	20.6	3	2	0.00	>0.05	
WB 10	DPW Channel Bridge	51	34	70.6	64.7	1	1	0.00	>0.05	
WB 11.2	S. Puerto Rico Dump	51	34	58.8	58.8	1	1	0.03	>0.05	
WB 12	Smiling Cove Marina	51	34	3.9	26.5	3	1	0.01	>0.05	
WB 12.1	American Memorial Park	51	34	33.3	29.4	1	1	0.01	>0.05	
WB 13	Outer Cove Marina	51	34	0.0	17.6	3	2	0.01	>0.05	
WB 14	Micro Beach	51	34	9.8	26.5	3	1	0.01	>0.05	
WB 15	Hyatt Hotel	51	34	15.7	14.7	2	2	0.00	>0.05	
WB 16	Dai-Ichi Hotel	51	34	21.6	17.6	2	2	0.01	>0.05	
WB 17	Drainage #1	51	34	31.4	41.2	1	1	0.02	>0.05	
WB 18	Samoan Housing area	51	34	11.8	14.7	2	2	0.00	>0.05	
WB 19	Hafa-Adai Hotel	51	34	23.5	32.4	2	1	0.00	>0.05	
WB 20	Drainage #2	51	34	33.3	32.4	1	1	0.06	0.020	*
WB 21	Garapan Fishing Dock	51	34	25.5	41.2	1	1	0.05	0.050	*
WB 22	Garapan Beach	51	34	3.9	32.4	3	1	0.00	>0.05	
WB 23	Drainage #3	51	34	31.4	44.1	1	1	0.00	>0.05	
WB 24	Chalan Laulau Beach	51	34	7.8	5.9	3	3	0.17	0.000	***

Table 7. Summary of beach monitoring locations and *Enterococci* bacteria violations for Saipan: a ranking of 1 = non-supportive, 2 = partially supportive, and 3 = fully supportive. Regression analysis results are presented as P values.


Table 7. Cont.


Beach Identifier	Beach Name	2006 Sample Size (n)	2007 Sample Size (n)	Percent Violations (Enterococci) 2006	Percent Violations (Enterococci) 2007	Rankings 2006	Rankings 2007	R ²	P Valu	Ie
WB 25	San Jose Beach	51	34	7.8	8.8	3	3	0.00	>0.05	
WB 26	Civic Center Beach	51	34	7.8	8.8	3	3	0.00	>0.05	
WB 27	Diamond Hotel	51	34	5.9	11.8	3	2	0.01	>0.05	
WB 28	Grand Hotel	51	34	5.9	5.9	3	3	0.00	>0.05	
WB 29	Community School Beach	51	34	5.9	8.8	3	3	0.08	0.009	**
WB 30	Sugar Dock	51	34	17.6	20.6	2	2	0.08	0.005	**
WB 31	CK District #2 Drainage	51	34	9.8	17.6	3	2	0.03	>0.05	
WB 32	CK District #4 Lally Beach	51	34	3.9	8.8	3	3	0.00	>0.05	
WB 33	Chalan Piao Beach	51	34	9.8	11.8	3	2	0.03	>0.05	
WB 34	Hopwood School Beach	51	34	19.6	20.6	2	2	0.10	0.004	**
WB 35	San Antonio Beach	51	34	5.9	5.9	3	3	0.02	>0.05	
WB 36	Pacific Islands Club (PIC)	51	34	7.8	2.9	3	3	0.00	>0.05	
WB 37	San Antonio Lift Station	51	34	7.8	5.9	3	3	0.00	>0.05	
NEB 1	Grotto Cave	24	26	4.2	3.8	3	3	0.06	>0.05	
NEB 2	Bird Island Beach	24	26	24.9	15.4	2	2	0.05	>0.05	
NEB 3	Jeffrey's Beach	24	26	37.5	38.5	1	1	0.08	>0.05	
NEB 4	Old Man by the Sea	24	26	24.9	23.1	2	2	0.09	0.050	*
NEB 5	Marine Beach	24	26	0.0	19.2	3	2	0.00	>0.05	
NEB 6	Tank Beach	24	26	8.3	15.4	3	2	0.00	>0.05	
NEB 7	Hidden Beach	24	26	33.3	26.9	1	1	0.04	>0.05	
SEB 2	North Laulau Beach	24	26	16.7	15.4	2	2	0.39	0.001	***
SEB 3	South laulau Beach	24	26	4.2	34.6	3	1	0.43	0.001	***
SEB 4	Obyan	24	26	0.0	11.5	3	2	0.00	>0.05	
SEB 5	Ladder Beach	24	26	12.5	3.8	2	3	0.02	>0.05	

Figure 9. Average *enterococci* bacteria levels at Saipan west beach monitoring sites during rain (daily value > 0.10 inches), and non-rain events for 2006.



Site





Site

Beach Identifier	Beach Name	Island Name	Longitude	Latitude	2006 Sample Size (n)	2007 Sample Size (n)	Percent Violations (Enterococci) 2006	Percent Violations (Enterococci) 2007	Rankings 2006	Rankings 2007
T1	Unai Masalok Beach	Tinian	15.0211	145.6525	26	19	0.0	10.5	3	2
T2	Unai Dangkolo Beach	Tinian	15.0329	145.6467	26	19	3.8	0.0	3	3
Т3	Unai Babui	Tinian	15.0775	145.6197	26	19	0.0	15.8	3	2
T4	Unai Chulu	Tinian	15.0705	145.6126	26	19	0.0	0.0	3	3
T5	Leprosarium Beach I	Tinian	14.9796	145.6099	26	19	3.8	10.5	3	2
T6	Leprosarium Beach II	Tinian	14.9875	145.6056	26	19	3.8	10.5	3	2
T7	Tachogna Beach	Tinian	14.9511	145.6285	26	19	0.0	5.3	3	3
Т8	Taga Beach	Tinian	14.9542	145.6270	26	19	0.0	5.3	3	3
Т9	Harbor	Tinian	14.9625	145.6171	26	19	7.7	0.0	3	3
T10	Kammer Beach	Tinian	14.9619	145.6228	26	19	0.0	0.0	3	3
R1	Coral Garden Beach	Rota	14.1161	145.1667	23	27	0.0	3.7	3	3
R2	Kokomo Beach Club	Rota	14.1294	145.1598	23	27	8.7	14.8	3	2
R3	Mobile Station Storm Drainage	Rota	14.1369	145.1428	23	27	0.0	0.0	3	3
R4	East Harbor Dock	Rota	14.1371	145.1416	23	27	0.0	0.0	3	3
R5	Tweksberry Beach	Rota	14.1311	145.1282	23	27	0.0	0.0	3	3
R6	West Harbor Marina	Rota	14.1335	145.1309	23	27	0.0	0.0	3	3
R7	District #2 Storm Drainage	Rota	14.1408	145.1379	23	27	4.3	22.2	3	2
R8	District #1 Strom Drainage	Rota	14.1422	145.1394	23	27	0.0	11.1	3	2
R9	Veterans Memorial Beach	Rota	14.1674	145.1787	23	27	4.3	0.0	3	3
R10	Teteto Beach	Rota	14.1702	145.1861	23	27	0.0	0.0	3	3
R11	Guata Beach	Rota	14.1723	145.1945	23	27	0.0	3.7	3	3
R12	Swimming Hole	Rota	14.1823	145.2091	23	27	8.7	0.0	3	3

Table 8. Summary of beach monitoring locations and *Enterococci* bacteria violations for Tinian and Rota: a ranking of 1 = non-supportive, 2 = partially supportive, and 3 = fully supportive.

Beach Identifier	Beach Name	2006 Sample Size (n)	2007 Sample Size (n)	Percent Violations (Enterococci) 2006	Percent Violations (Enterococci) 2007	Rankings 2006	Rankings 2007
M1	Managaha Beaches	30	25	6.7	4.0	3	3
M2	Managaha Beaches	30	25	6.7	0.0	3	3
M3	Managaha Beaches	30	25	3.3	0.0	3	3
M4	Managaha Beaches	30	25	0.0	0.0	3	3
M5	Managaha Beaches	30	25	0.0	0.0	3	3
M6	Managaha Beaches	30	25	3.3	0.0	3	3
M7	Managaha Beaches	30	25	6.7	0.0	3	3
M8	Managaha Beaches	30	25	0.0	0.0	3	3
M9	Managaha Beaches	30	25	3.3	0.0	3	3
M10	Managaha Beaches	30	25	3.3	4.0	3	3
M11	Managaha Beaches	30	25	6.7	0.0	3	3

Table 9. Summary of beach monitoring locations and *Enterococci* bacteria violations for Managaha: a ranking of 1 = non-supportive, 2 = partially supportive, and 3 = fully supportive.

Lagoon and Coral Reef Biocriteria Monitoring Programs

BACKGROUND AND METHODOLOGY

Many monitoring programs that assess waterbody health with water quality data only are not sufficient to detect changes over time due to infrequent sampling and low sample sizes. One way to enhance water quality data collection may be through the use of continuous recording instruments. However, this approach is very expensive for multiple waterbodies. A more cost and time efficient method is to gather data on the distribution and abundances of organisms that live within the waterbodies that are to be assessed. For all island nations with tropical marine waters these marine communities will shift in response to nutrients, sediment loads, and turbidity (Rogers, 1990, Telesnicki and Goldberg, 1995). As a result, the CNMI uses several measures of the coral reef and seagrass community as biological criteria for waterbody evaluation described herein.

The CNMI interagency marine monitoring team (MMT) was initially established in 1997 to help understand the current conditions of their coral reefs and associated resources. It has expanded over the past 7 years to improve data collection techniques, data accuracy, staff training, and spatial coverage (Houk and Starmer, 2008, Houk and Van Woesik, 2006, 2008). It is the goal of the CNMI Marine Monitoring Team to continually assess our reefs as population and development grow, and provide pertinent data to trigger management action. DEQ plays a major role in the MMT through its marine biologist, non-point source pollution program, and laboratory program. Data from two monitoring efforts are used in this report to categorize waterbodies in accordance with EPA guidance materials: 1) Saipan Lagoon seagrass and 2) nearshore coral reef monitoring. Currently, no EPA criteria exist for the evaluation of seagrass beds and coral reefs, however, this report logically extended the existing EPA guidance material to provide for the evaluation of waterbodies based upon our benthic communities.

Lagoon benthic communities were evaluated by calculating a ratio of seagrass to turf/macroalgae coverage based upon replicated benthic assessment transects during each year (Houk and van Woesik 2008). Only *Halodule uninervis* seagrass beds were used in this evaluation because they show the greatest affinities with watershed population and development (Houk and van Woesik 2008), and are widely distributed throughout the lagoon. The data collected here represent the highest level of technical components based upon EPA guidance material. All data were collected and analyzed by a professional biologist for interpretation using statistically appropriate techniques.

Coral reef benthic communities were evaluated by calculating a ratio of coral/crustose coralline algae (CCA), favorable attributes for sustainable coral assemblages, to turf/macroalgae, unfavorable attributes (Rogers, 1990, Richmond, 1997, Fabricius and De'ath, 2001, Houk and van Woesik 2006). Ratio's were calculated from statistically validated benthic surveys (Houk and van Woesik 2007). A second measure used to evaluate waterbody 'health' was coral species richness per unit area. This metric builds

upon significant affinities between species richness and watershed population and development in the CNMI (Houk and van Woesik, in review).

ALUS rankings were derived from trend data, comparing replicated measures from the 2006 305(b) report to the present using paired t-tests following:

Degree Aquatic Life Use Support	Criteria			
One step increase (i.e., from 'not' to 'partially' supportive, or from 'partially' to 'fully supportive'	Significant increase in biological metrics			
No change	No significant difference			
One step decrease (i.e., from 'partially' to 'not' supportive, or from 'fully' to 'partially supportive'	Significant decrease in biological metrics			

RESULTS AND DISCUSSION

The only differences in ALUS rankings for seagrass beds within the Saipan Lagoon were improvements from partially to fully supportive ranking for stations located in the southern lagoon, affiliated with the sewer line improvements noted in the water quality section above (Figure 11). This is encouraging and if positive trends continue we aim to request a de-listing of these waters from our 303(d) list in 2010. However, the numerous seagrass beds in the Saipan Lagoon which were non-supportive for aquatic life use (Figure 11) mostly represent the marine waters adjacent to large, steep sloping, populated watersheds. Runoff that passes through these watersheds drains into the lagoon during storm events, carrying associated pollutants. Watershed plans to deal with these regions have been established in many cases, however, capital funding to implement the construction of large-scale best-management-practices impedes further progress. The northernmost, non supportive seagrass habitats are attributed to failing sewer collection facilities as populations are relatively low but overflows are common. As a result of nutrient and bacteria input seagrass habitats become dominated by macroalgae (Calurpa, Dictyota, and Acanthophora mainly) compared with seagrass (Halodule uninervis). Results from beach water quality monitoring agree with benthic data showing high bacteria levels in regions with high abundances of macroalgae. Similar to our coral reef reporting below, we aim to utilize trend data in the future to estimate the direction (positive or negative) biological assemblages are heading, and ranking the associated waterbodies in accordance with trends, and not single assessment data.

Twenty one coral reef surveys were conducted for waterbody evaluation (Figure 12). Of the twenty one locations surveyed, 5 were non-supportive, 11 were partially supportive, and 5 were fully supportive for aquatic life use (Table 10). Compared with the 2006 rankings there was an overall decline in the number of fully supportive sites from 10 to 5, as most sites are now classified as partially supportive. This is attributed to our generation of trend data that has enabled us to more accurately estimate the direction (positive or negative) biological assemblages are heading. Not supportive rankings were suspected to be a consequence of sedimentation, polluted groundwater discharge, and the proximity to boat marinas. Partially supportive sites are all associated with large volume watersheds with varying levels of suspect pollution. Further studies are currently underway to formulate a predictive knowledge regarding the expected benthos abundances given a set of watershed statistics. DEQ aims to continue their monitoring program and further trend data collection for our coral reefs. This will help to evaluate the effectiveness of management strategies and action, and allow for a priority ranking of remaining, problematic watersheds. Figure 11. A map showing all *Halodule* seagrass habitats throughout the Saipan lagoon color coded as follows: red = non-supportive, yellow = partially supportive, green = fully supportive.





Figure 12. A map of coral reef biocriteria monitoring locations used in the present assessment.



Site Name	Island	Change in Coral Species Richness	P- value	Change in Benthic Substrate Ratio	P-value	ALUS
AGU - 1	Aguijan					Fully Supportive
NEB 2 - Bird Island	Saipan	-1.25	0.07	-0.75	0.02	Partially Supportive
NEB 6 - Tank Beach	Saipan					Partially Supportive
T2 - Unai Dangkolo	Tinian					Partially Supportive
AGU - 2	Aguijan					Fully Supportive
Sasanhaya	Rota	-0.66	0.30	-1.21	<0.01	Partially Supportive
SEB 3 - Lau Lau #1	Saipan	-0.44	0.48	-0.18	0.11	Not Supportive
SEB 4 - Obyan	Saipan					Fully Supportive
SEB 6	Saipan	-6.00	<0.01	-1.10	<0.01	Partially Supportive
Talakhaya	Rota	-0.06	0.89	0.10	0.01	Partially Supportive
T3 - Unai Babui	Tinian	0.13	0.82			Not Supportive
Boy Scout	Saipan	-2.31	<0.01	-0.28	0.11	Partially Supportive
T6 - Leprosarium II	Tinian	0.56	0.35	-1.41	0.01	Partially Supportive
R1 - Coral Gardens	Rota	0.44	0.42	-0.29	0.25	Fully Supportive
SEB 2 - Lau Lau #2	Saipan	0.13	0.84	-0.18	0.28	Partially Supportive
M1 - M11 Managaha Island	Managaha					Fully Supportive
T7 - Tachogna	Tinian					Not Supportive
R12	Rota	-0.88	0.09	0.07	0.06	Not Supportive
R6 - West Harbor	Rota	-0.38	0.57	-0.46	0.04	Not Supportive
Santa Margarita	Rota	0.56	0.41	-0.32	0.02	Partially Supportive
R9	Rota	0.56	0.41			Partially Supportive

Table 10. Aquatic life use support rankings based upon coral reef monitoring data.

Integrated 305b and 303d Waterbody Classification

(CALM) WATERBODY CLASSIFICATION

EPA Consolidated Assessment and Listing Methodology (CALM) was used to classify each waterbody based upon water quality and biocriteria assessments as follows:

- <u>Category 1</u> Water body meets all designated uses. No use is impaired.
- <u>Category 2</u> Water body meets some of the designated uses. There is insufficient data to evaluate any remaining designated uses.
- <u>Category 3</u> There are insufficient data to evaluate any designated uses.
- <u>Category 4a</u> Water body is impaired for one or more designated uses, but a TMDL has already been prepared and completed.
- <u>Category 4b</u> Water body is impaired for one or more designated uses, but a TMDL is not necessary because other pollution control requirements are reasonably expected to result in the attainment of the water quality standard in the near future.
- <u>Category 4c</u> Water body is impaired for one or more designated uses, but a TMDL is not necessary because a pollutant does not cause the impairment.
- <u>Category 5</u> Water body is impaired, and a TMDL is required [303(d) list].

Each water quality or biocriteria monitoring location was considered to be representative of water quality conditions within a 250 m radius. This distance is based upon CNMI water quality standards for sample violations. Assessments from water quality and biocriteria data were used to rank waterbodies following EPA guidance materials; all 'partially supportive' or 'non-supportive' rankings are defined as not meeting the designated use and the waterbody is considered 'impaired'. If remedial actions have resulted in a positive change in the water quality data and waterbody ranking, the site is now being closely monitored for future removal from CNMI's 303(d) list, pending a second significant positive trend being noted in 2010. Because biological criteria data are better indicators for aquatic life support (due to relatively small water quality sample sizes), these data were used to formulate final rankings when they are available.

The cause for listing all impaired waters is listed in table 11 following:

- 1 New waters listed as impaired due to present *Enterococci* bacteria violations.
- 2 Waters listed as impaired due to past (2002 2006) *Enterococci* bacteria violations.
- 3 Waters listed as impaired due to biological criteria data.
- 4 and 5 Waters listed as impaired due to orthophosphate (4) and dissolved oxygen (5) criteria violations (2002 present). As described above described above, the development of the CNMI Water Quality Standards were largely based upon the review of existing water quality standards for other tropical islands, and unfortunately not specific to the CNMI. Thus, waterbodies that were 303(d) listed solely because of these criteria are of lowest priority for enhanced management consideration.

Throughout CNMI's 53.7 km of beach coastline 69% was assessed during 2006 – 2007 (Table 12). CNMI wide results indicate that 89% of all monitored waterbodies were impaired and placed in CALM category 5, and remain 303(d) listed for various reasons (Table 11 and 12). Saipan has the largest percentage of impaired waters (94%) due to bacteria violation and biological data. The impaired waters of Tinian (100%) and Rota (85%) are listed mainly due to historical nutrient data, an artifact of CNMI's stringent orthophosphate and dissolved oxygen water quality standards that do no represent ambient conditions. As discussed at length in our 2004 report, nutrient standards were adopted from the state of Hawaii's water quality standards (volcanic islands in Hawaii versus raised limestone islands in the CNMI), and are not indicative of ambient conditions in the CNMI. While their revision remains a top priority, DEQ does not have the technical staff available and despite many attempts to collaborate with the University of Guam Water and Energy Research Institute, we are not yet able to resolve this matter.

303(D) PRIORITY LIST

A TMDL priority listing was created to accompany all waters placed on the 303(d) list, or category 5 waters (Table 11). All waterbodies were listed as A or B as follows:

- A Bio-criteria or *Enterococci* data analyses resulted in a non-supportive ranking. Waters are heavily used by residents and tourists. Waters have several suspect sources of pollution. These waters are currently the top priority for TMDL listing.
- B Bio-criteria or *Enterococci* data analyses resulted in a partially, or not supportive ranking. Waters are not heavily used by residents and tourists. A suspect pollution source may or may not be known. These waters are currently the medium priority for TMDL listing.
- C Contemporary bio-criteria or *Enterococci* data analyses resulted in a fully supportive ranking. Past data relating to single samples bacterial violations or. dissolved oxygen and/or orthophosphate data analyses resulted in a non-supportive ranking, and serve as the only reason for placement on the 303(d) list. It is believed that many waterbodies exceed these standards naturally, as discussed above. These waters are currently the low priority for TMDL listing.

Beach Identifier	Beach Name	Island Name	2006 Enterococci Rankings (Recreational Use)	2007 Enterococci Rankings (Recreational Use)	2006/7 Bio-Criteria Ranking (ALUS)	(CALM) Waterbody Category	Impairment Cause	Priority Listing
WB 1	Wing Beach	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	В
WB 2	PauPau Beach	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4, 5	В
WB 3	Nikko Hotel	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4, 5	В
WB 4	San Roque School	Saipan	Partially supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4, 5	В
WB 5	Plumeria Hotel	Saipan	Fully supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4, 5	В
WB 6	Aqua Resort Hotel	Saipan	Fully supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4	А
WB 7	Tanapag Meeting Hall	Saipan	Not supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 8	Central Repair Shop	Saipan	Partially supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 9	Sea Plane Ramp	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	2, 4, 5	В
WB 10	DPW Channel Bridge	Saipan	Not supportive	Not supportive	no data within 250 m of point	5	1, 2, 4, 5	А
WB 11.2	S. Puerto Rico Dump	Saipan	Not supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 12	Smiling Cove Marina	Saipan	Fully supportive	Not supportive	no data within 250 m of point	5	1, 2, 4, 5	А
WB 12.1	American Memorial Park Drainage	Saipan	Not supportive	Not supportive	no data within 250 m of point	5	1, 2, 4, 5	В
WB 13	Outer Cove Marina	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	А
WB 14	Micro Beach	Saipan	Fully supportive	Not supportive	no data within 250 m of point	5	1, 2, 4, 5	В
WB 15	Hyatt Hotel	Saipan	Partially supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4, 5	В
WB 16	Dai-Ichi Hotel	Saipan	Partially supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4, 5	В
WB 17	Drainage #1	Saipan	Not supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	В
WB 18	Samoan Housing area	Saipan	Partially supportive	Partially supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 19	Hafa-Adai Hotel	Saipan	Partially supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 20	Drainage #2	Saipan	Not supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 21	Garapan Fishing Dock	Saipan	Not supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 22	Garapan Beach	Saipan	Fully supportive	Not supportive	Non Supportive	5	1, 2, 3, 4, 5	А
WB 23	Drainage #3	Saipan	Not supportive	Not supportive	Partially Supportive	5	1, 2, 3, 4, 5	А
WB 24	Chalan Laulau Beach	Saipan	Fully supportive	Fully supportive	Partially Supportive	5	1, 3, 4, 5	А
WB 25	San Jose Beach	Saipan	Fully supportive	Fully supportive	Fully Supportive	1		
WB 26	Civic Center Beach	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	4, 5	С
WB 27	Diamond Hotel	Saipan	Fully supportive	Partially supportive	Fully Supportive	1		
WB 28	Grand Hotel	Saipan	Fully supportive	Fully supportive	Fully Supportive	1		
WB 29	Community School Beach	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	4, 5	С

Table 11. (CALM) waterbody classifications, impairment causes, and priority listings.

Table 11. Cont.

Beach Identifier	Beach Name	Island Name	2006 Enterococci Rankings (Recreational Use)	2007 Enterococci Rankings (Recreational Use)	2006/7 Bio-Criteria Ranking (ALUS)	(CALM) Waterbody Category	Impairment Cause	Priority Listing
WB 30	Sugar Dock	Saipan	Partially supportive	Partially supportive	Partially Supportive	5	1, 2, 3, 4, 5	В
WB 31	CK District #2 Drainage	Saipan	Fully supportive	Partially supportive	Partially Supportive	5	1, 2, 3, 4, 5	В
WB 32	CK District #4 Lally Beach	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	2, 4, 5	В
WB 33	Chalan Piao Beach	Saipan	Fully supportive	Partially supportive	Fully Supportive	5	1, 2, 4, 5	В
WB 34	Hopwood School Beach	Saipan	Partially supportive	Partially supportive	Fully Supportive	5	1, 2, 4, 5	В
WB 35	San Antonio Beach	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	1, 2, 4, 5	В
WB 36	Pacific Islands Club (PIC)	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	1, 2, 4, 5	В
WB 37	San Antonio Lift Station	Saipan	Fully supportive	Fully supportive	Fully Supportive	5	1, 2, 4, 5	В
NEB 1	Grotto Cave	Saipan	Fully supportive	Fully supportive	no data within 250 m of point	5	1	С
NEB 2	Bird Island Beach	Saipan	Partially supportive	Partially supportive	Partially Supportive	5	1, 2, 3	В
NEB 3	Jeffrey's Beach	Saipan	Not supportive	Not supportive	no data within 250 m of point	5	1, 2, 4	В
NEB 4	Old Man by the Sea	Saipan	Partially supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	В
NEB 5	Marine Beach	Saipan	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	В
NEB 6	Tank Beach	Saipan	Fully supportive	Partially supportive	Partially Supportive	5	1, 2, 3, 4	В
NEB 7	Hidden Beach	Saipan	Not supportive	Not supportive	no data within 250 m of point	5	1, 2	В
SEB 2	North Laulau Beach	Saipan	Partially supportive	Partially supportive	Partially Supportive	5	1, 2, 3, 4	А
SEB 3	South laulau Beach	Saipan	Fully supportive	Not supportive	Not Supportive	5	1, 2, 3, 4	А
SEB 4	Obyan	Saipan	Fully supportive	Partially supportive	Fully Supportive	5	1	С
SEB 5	Ladder Beach	Saipan	Partially supportive	Fully supportive	no data within 250 m of point	5	1, 2	В
SEB 6	Coral Ocean Point	Saipan	Fully supportive	Partially supportive	Partially Supportive	5	1, 3	В
SEB 8	Boy Scout Beach	Saipan	No Data	No Data	Partially Supportive	5	3	В
M1	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M2	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M3	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M4	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M5	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M6	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M7	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M8	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		

Table 11. Cont.

Beach Identifier	Beach Name	Island Name	2006 Enterococci Rankings (Recreational Use)	2007 Enterococci Rankings (Recreational Use)	2006/7 Bio-Criteria Ranking (ALUS)	(CALM) Waterbody Category	Impairment Cause	Priority Listing
M9	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M10	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
M11	Managaha Beaches	Managaha	Fully supportive	Fully supportive	Fully Supportive	1		
T1	Unai Masalok Beach	Tinian	Fully supportive	Partially supportive	no data within 250 m of point	5	2, 4	В
T2	Unai Dangkolo Beach	Tinian	Fully supportive	Fully supportive	Partially Supportive	5	1, 3, 4	С
T3	Unai Babui	Tinian	Fully supportive	Partially supportive	Not Supportive	5	1, 2, 3, 4	В
T4	Unai Chulu	Tinian	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	В
T5	Leprosarium Beach I	Tinian	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	В
T6	Leprosarium Beach II	Tinian	Fully supportive	Partially supportive	Partially Supportive	5	1, 2, 3, 4	В
T7	Tachogna Beach	Tinian	Fully supportive	Fully supportive	Not Supportive	5	3, 4	В
T8	Taga Beach	Tinian	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
Т9	Harbor	Tinian	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
T10	Kammer Beach	Tinian	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
R1	Coral Garden Beach	Rota	Fully supportive	Fully supportive	Fully Supportive	1		
R2	Kokomo Beach Club	Rota	Fully supportive	Partially supportive	no data within 250 m of point	5	2, 4	В
R3	Mobile Station Storm Drainage	Rota	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
R4	East Harbor Dock	Rota	Fully supportive	Fully supportive	no data within 250 m of point	5	4	С
R5	Tweksberry Beach	Rota	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
R6	West Harbor Marina	Rota	Fully supportive	Fully supportive	Not Supportive	5	1, 3, 4	А
R7	District #2 Storm Drainage	Rota	Fully supportive	Partially supportive	no data within 250 m of point	5	1, 2, 4	В
R8	District #1 Strom Drainage	Rota	Fully supportive	Partially supportive	no data within 250 m of point	5	2, 4	В
R9	Veterans Memorial Beach	Rota	Fully supportive	Fully supportive	no data within 250 m of point	1		
R10	Teteto Beach	Rota	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
R11	Guata Beach	Rota	Fully supportive	Fully supportive	no data within 250 m of point	5	1, 4	С
R12	Swimming Hole	Rota	Fully supportive	Fully supportive	Not Supportive	5	2, 3, 4	С
R13	Santa Margarita	Rota	No Data	No Data	Partially Supportive	5	3	В
R14	Sasanhaya	Rota	No Data	No Data	Partially Supportive	5	3	В
R15	Talakhaya	Rota	No Data	No Data	Partially Supportive	5	3	В
AGU - 2	-	Aguijan	No Data	No Data	Fully Supportive	1		
AGU - 1	-	Aguijan	No Data	No Data	Fully Supportive	1		

Island	Total Coastline (km)	Total Beach Coastline (km)	Total Coastline Monitored for Recreational Use (Enterococci) (km)	Total Coastline Monitored in (Bio- Criteria Program, ALUS) (km)	(CALM) Category 1 (not impaired, sufficient data) (km)	(CALM) Category 5 (impaired)
Saipan	68.96	28.57	25	18	1.5	23.5
Managaha	1.04	1.04	1.04	1.04	1.04	0
Tinian	51.36	7.08	5	2	0	5
Aguijan	11.57	0	0	1	1	0
Rota	50.52	17.05	6	3.5	1	6.5

Table 12. Final statistics for CNMI waters based upon (CALM) classification.

Relevant Issues Associated With Water Quality Permitting and Pollution Prevention Programs

The Division of Environmental Quality (DEQ) and other CNMI government agencies implement several environmental programs to control point and non-point sources of pollution. The two most relevant are the Earthmoving and Erosion Control and Non-Point Source Pollution Programs. The former represents a permitting based program while the latter focuses more on public education and demonstration projects dealing with land based pollution. DEQ's NPS program also coordinates with EPA, NOAA, and the CNMI Coastal Resources Management Office to implement the requirements of the Section 6217 Coastal Non-Point Source Pollution Programs.

CURRENT PROGRAM ACTIVITIES AND PROJECTS RELEVANT TO 303(D) LISTED WATERS

Laolao Bay Stormwater Control (Relevant to Waters for 'SEB 2, 3')

On Saipan's east coast, the coral reefs of Laolao Bay are severely threatened by sediment from eroding dirt and gravel roads, streambeds, and upland runoff including septic system percolation. Funding and community effort is being devoted to reducing sedimentation and nutrient delivery through best management practices. In 2006, hundreds of community volunteers, Laolao Bay stakeholders, and local and federal agencies gathered for a revegetation effort of the upper badlands area. As a result, 4900 tree and grass seedlings were planted in 7 of 24 acres. In 2008, Phase II of the revegetation project will commence to further revegetate the remaining barren land causing sediment runoff into the bay. In addition, architectural and engineering designs have been completed for the improvement of Laolao Bay Road. This project includes road stabilization and stormwater controls along the road. DEQ is also in the process of gathering watershed data to find permanent solutions by linking data and management decisions. These efforts have been ongoing with funding support from the CNMI Coral Reef Initiative Program.

Obyan Beach Stormwater Control (Relevant to Category 4b Waters for'SEB 4')

Obyan Beach is another dive site frequented by residents and tourists that has been exposed to sedimentation runoff into the ocean from gravel roads. CRMO and DEQ have joined efforts to address the runoff problem by completing engineering designs that would improve the road and water quality of runoff waters. In 2007, The Mariana Islands Nature Alliance (MINA), a local grassroots organization along other with government, and non-government organizations joined to address erosion concerns at Obyan. Several barriers for dispersing and filtering the runoff were installed as a nonpoint source pollution prevention best management practice. The re-establishing of plants has stabilized many impacted areas near the site and protects it from further damage. Construction of the A&E designs for road and drainage improvements remains a top priority.

The group also blocked off the area to prevent vehicular access leading to the beach area.

Talakhaya Restoration Project (Relevant to Category 4b Waters for 'Talakhaya')

The Talakhaya watershed in Rota, CNMI, contains Rota's only perennial streams that support domestic uses. For decades, this watershed has suffered from frequent wildfires intentionally set by hunters to create new vegetation growth to attract Sambar deer. The fires remove vegetation and cause significant soil erosion and slumping, particularly during the rainy season. The greatest threat to this water resource and the health of coral reef communities is runoff containing sediments and nutrients. The natural resource management agencies of the CNMI continue to make important strides in the effort to prevent, control, and reduce the occurrences of wildfires.

Between 2006 and 2008, efforts to revegetate the badlands area have been ongoing amongst the Rota community. Over 200 Earth Team Volunteers participated in the effort and about 19,000 grass and tree seedlings were casted. Seventy-five (75%) percent of the plants were native species. The project also established the Luta Livelihoods Initiative providing jobs for the unemployed to work on the revegetation project. The projects developed partnerships amongst the community, local and federal government agencies. Similar to the Laolao Bay project, a second phase will commence in the summer of 2008. Monitoring of the marine water quality by the DEQ Laboratory is ongoing on an 8-week cycle followed by regular monthly sampling. Monitoring conducted by the CNMI's Marine Monitoring Team (MMT) over the last five years shows that turf algae, which grow rapidly in response to nutrient addition associated with upland sedimentation, have begun to dominate Talakhaya's nearshore coral reef community. In addition, observations from MMT surveys in 2005 show an increase in heterotrophic organisms (i.e., sponges, bivalves, soft corals, etc.), presumably as a result of increased phytoplankton blooms (food for heterotrophs) and decreased light and oxygen levels. As a result, the Talakhaya watershed has been identified as a Threat/Focus Area in the CNMI's Coral Reef Initiative Local Action Strategies and listed as a Category I Watershed in the CNMI's Unified Watershed Assessment.

Some recent actions taken to address this issue include meetings with the Rota watershed committee to discuss the revegetation and education/outreach efforts for Talakhaya. As a result, a watershed retoration plan has been developed and funding has been granted through the Coral Reef Initiative program to implement the plan which includes revegetation of the barren areas on the watershed, an outreach and education plan, and water quality and marine monitoring.

Garapan Drainage Improvement Designs (Relevant to Category 4b Waters for WB 12b, 14-17)

Two sub-drainages within the Garapan district have been identified as significant contributors to tainted water quality in the Garapan Lagoon. Through several outreach campaigns and meetings with CNMI's inter-agency watershed group this information has been disseminated to the public and elected governmental officials. A conceptual, remedial wetland ponding system design was prepared by DEQ and presented to government officials to seek funding for proper planning designs and construction. Currently, two of Saipan's most polluted sub-drainages have completed designs, received permits, and construction funds are earmarked for the establishment of stormwater treatment wetlands. Because of these advances several waterbodies (noted above) were listed as category 4b. The DEQ water quality and marine monitoring programs will serve to examine the effectiveness of stormwater treatment infrastructure.

Groundwater Assessment

Numeric Groundwater Standards


In December 2004, regulations designating groundwater management zones (GMZs) on Saipan were promulgated. Three zones, Class I, II, and III were created based on groundwater quality, availability of recharge, susceptibility to degradation, and present and future land use (Figure 13). Class I GMZs are critical groundwater protection areas capable of supplying high quality fresh water, and receive the highest level of environmental protection. Class I GMZs include all high level (perched) aquifers, municipal well fields, and watersheds contributing to surface infiltration to springs and fresh water systems. Class II GMZs are important protection areas considered capable of supplying good quality groundwater, but generally of lower quality (e.g. higher chlorides concentration) that Class I GMZs. Class II GMZs include relatively high quality basal groundwater lens resources with chloride concentrations less than 500 mg/l. Class III GMZs are ares providing recharge to primarily brackish aquifers, having some intrinsic value as a resource to supply deslination plants, but primarily of lower value than groundwater found in Class I and II GMZs. Class III GMZs include the groundwater resources with chloride concentrations in excess of 500 gm/l.


Summary Results of Groundwater Monitoring

The CNMI Groundwater Protection and Management Act was enacted into law in 1988. The first set of Well Drilling regulations were adopted in 1992 and later amended in 1994, and most recently in 2004. The well drilling regulations set standard requirements and criteria for licensed well drillers, well construction, setback distances, and requirements for operating of new and renewed wells. As part of operations, annual monitoring of chlorides, conductivity, total dissolve solids, pH, total coliform and monthly withdrawal rate of water are required for all wells.

With the new GIS program and hand held GPS units, DEQ will continue to improve the database of all private wells with information on operation date, location, and monitoring data. The database is its early infantile stages with much need for improvement on quality control of missing or inaccurate data. It is envisioned that the data will be integrated into the CNMI GIS system. DEQ will be able to use the fully developed GIS system to identify existing sources of contamination and potential problems for proposed new and existing wells.

A general review of the sample data for the private wells shows that chlorides and conductivity gradually increase over time in many of the wells. In some wells, a reduction in the operating pressure has resulted in a decrease in conductivity and chlorides. (Note: Conductivity was believed to be a better indicator of increasing saltwater intrusion due to potential laboratory error associated with testing equipment for





chlorides). It is the current unofficial policy to limit all new wells to under a pumping rate of 20 gallons per minute unless there are unusual circumstances with high quality aquifer and special needs.

As DEQ laboratory capabilities increase, DEQ will continue requiring the testing of nitrates in private and municipal water wells used for drinking and other human consumptions. To be assured that the quality of groundwater being used by the local community is not contaminated from old military or current activities, testing for metals, volatile organic compounds, and synthetic organic compounds, pesticide and herbicide, radionuclides and other inorganic compounds were required as part of a source water assessment. In May 2000, DEQ and EPA region IX conducted an island wide sampling of all private wells for VOC's, metals, pesticides and herbicides on several wells. In 1999, DEQ started enforcing the Phase II/V chemical monitoring and is currently underway. Several private well were found to have exceeded the EPA Maximum Contaminant Level (MCL) for drinking water.

The USGS office in the CNMI was closed in late 2005, and as a result, the Safe Drinking Water/Groundwater Management Program began monthly monitoring of the static water level in the 14 USGS wells on Saipan. The program hopes to be able to use this data in the management of withdrawal rates from the aquifers on Saipan.

Literature Cited

- Clarke, K.R., Warwick, R.M. 2001. Change in Marine Communities: An Approach to Statistical Analysis and Interpretation. 2nd edition, PRIMER-E, Plymouth, UK.
- CNMI Department of Natural Resources, 1989. Commonwealth of the Northern Mariana Islands Wetlands Conservation Priority Plan, An Addendum to the 1985 Statewide Comprehensive Outdoor Recreational Plan. CRM Office, CNMI.
- Fabricius, K., De'ath, G. 2001. Environmental factors associated with the spatial distribution of crustose coralline algae on the Great Barrier Reef. Coral Reefs 19, 303-309.
- Houk, P. 1999. State of the reef report for 5 sites on Rota Island, Commonwealth of the Northern Mariana Islands. CNMI Division of Environmental Quality unpublished report.
- Houk, P. 2000. State of the reef report for Saipan Island, Commonwealth of the Northern Mariana Islands. CNMI Division of Environmental Quality unpublished report.
- Houk, P., Starmer, J. 2004. Long-Term Marine and Water Quality Monitoring Plan. CNMI Division of Environmental Quality and Coastal Resources Management Office, Saipan, CNMI.
- Houk, P., Van Woesik, R. 2006. Coral reef benthic video surveys facilitate long-term monitoring in the Commonwealth of the Northern Mariana Islands: toward an optimal sampling strategy. Pac. Sci. 60(2), 175-188.
- Karig DE. 1971. Structural history of the Mariana Island Arc System. Geological Society of American Bulletin. 82, 323-344.
- Lapointe, B.E. 1997. Nutrient Thresholds for Bottom-up Control of Macroalgal Blooms on Coral Reefs in Jamaica and Southeast Florida. Limn. Ocean. 42(5), 1119-1131.
- Littler, M.M., Littler, D.S. 1985. Factors controlling relative dominance of primary producers on biotic reefs. In: *Proceedings of the Fifth International Coral Reef Congress*, Tahiti 4, 35-40.
- Meesters, E.H., Hilterman, M., Kardinaal, E., Keetman, M., De Vries, M., Bak, R.P.M. 2001. Colony size-frequency distributions of scleractinian coral populations: Spatial land interspecific variation. Mar. Eco. Prog. Ser. 209, 43-54.

Myers, R.F. 2000. Micronesian reef fishes. 3rd Edition. Coral Graphics, Guam.

- Mrozowski CL, Hayes DE. 1980. The evolution of the Parece Vela Basin, eastern Philippine Sea. Earth and Planetary Sci. Lett. 46, 49-67.
- Randall, R.H. 1995. Biogeography of reef-building corals in the Mariana and Palau Islands in relation to back-arc rifting and the formation of the Eastern Philippine Sea. Nat. Hist. Res. 3(2), 193-210.
- Richmond, R.H. 1997. Reproduction and Recruitment in Corals: Critical Links in the Persistence of Reefs. In C.E. Birkeland, *Life and Death of Coral Reefs*, Chapman & Hall, New York, NY, pp. 536.
- Rogers, C. S. 1990. Responses of coral reefs and reef organisms to sedimentation. Marine Ecology Progress Series 62, 185-202.
- Telesnicki, G.J., Goldberg, W.M. 1995. Effects of turbidity on the photosynthesis and respiration on two South Florida reef coral species. Bulletin of Marine Science 57(2), 527-539.
- U.S. Army Corps of Engineers, 2003. Water Infrastructure Development Plan for the Island of Saipan, Commonwealth of the Northern Mariana Islands. U.S. Army Corps Engineer District, Honolulu, Hawaii.
- US Fish and Wildlife Service, 1989. National Wetlands Inventory, Map of Saipan. CRM Office, CNMI.
- Valiela, I. 1995. *Marine Ecological Processes*, Springer-Verlag, New York, NY, pp. 686.